



Stock # TRL18424  
Last 5 31387

### Load King Model: *Signature Series 503/605 SS SFF*

(Signature Series - 60 Ton Hydraulic Detachable Gooseneck Reinforced for a Stinger, 2 Flip Axles and Single or Tandem Axle Jeep)

General		Subframe	
120,000# capacity in 12' load concentration with stinger		Frame reinforcing & connections for future stinger & 2 Flip axle (5 axles total)	
100,000 / 80,000 psi yield steel mainbeams		Air lift 3rd axle w/manual raise & lower valve, +3 / -3 off leveling valve	
Est. weight (lbs):	25,245 not incl. attachments, +/- 5%	Three 27,500 lb axles- 5" x 3/4" wall	
Overall length:	53' - 0" not incl attachments	Axle spacing: 54-1/2"	0
9' wide (deck and axles)	1,380	Twelve 275/70R22.5 H radials	0
Hendrickson Air-Ride		Twelve 8.25 x 22.5 hub piloted steel disc wheels	0
<b>Gooseneck</b>		16½ in. x 7 in. drum brakes, no ABS	0
Hydraulic non-ground bearing Scraper neck		Spring brakes on axle 2	0
Work lights on gooseneck		Three tail light package with strobes	0
12'-9" 110" & 86" swing w/conn for 36" flip box, 146" swing	0	Boom trough, open to tailgate	0
51" 5th wheel height - adjustable with 5 position ratchet		Flush mount bolsters with open wheel wells	0
High clearance frame recess with hydraulic frame lift support arm		Wide Load sign pockets (no sign)	0
Air-activated, self-locking pin on gooseneck, positive Safety lock		Lowered crossmembers in subframe	
13 HP Honda in base section w/ selector valve	300	Other options: none	0
Other Gooseneck options: none		0	
<b>Deck</b>		<b>Other</b>	
4 full depth 16 in. cambered deck beams		DOT rubber-mounted LED lights & sealed harness	
26 ft. deck length - flat	0	Mid ship turn signal w/ dual intensity rear marker lights	
13 Pair chain slots in outer flanges		Black rubber Load King mud flaps, conspicuity tape	
Alternating 10" & 4" crossmembers on 12 in. centers		Other general options: none	0
24 in. loaded deck height with 8" loaded ground clearance	0	Load King Black 2-part polyurethane	0
2" Apitong (nominal) in track area bolted at all board ends		<b>Attachments included:</b>	
Open in center of deck	0	Connections & reinforcing for future 14' 1" stinger	0
Outriggers: 13 Pair swing out - removable		Addl spreader bar options: none added	
Wide Load Package- gussets behind each outrigger		Connections & reinforcing for future 4th & 5th axle flip	0
<b>Boxed Front Approach</b>		Addl. Flip axle options: none added	
<b>Bent D-rings - 6 per side</b>		<b>Special Options</b>	
Recessed last 8 ft. of deck with pierced steel plate		<b>Load King - Elk Point, SD</b>	Price Est Wt
Pierced Steel tool box - 60" at front	\$0 0		
30" front flip ramps - bridge style <u>spring assisted</u>			
32 degree radius to subframe - ramp to subframe			